BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41617

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

ame of Work: Improvements to drains cross roads of munigurappa layout in amruthahalli in ward o.07 Byataranapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KIRAN GOWDA D (SRI CHANNAKESHAWA ENTERPRISES)	
				In Figures	In Words
1	357	Removing and refixing stone slabs of drains and pointing in CM(1:3)	Sqm	94.05	Rupees Ninety Four and Five Paise Only
2	321.75	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	Cum	116.44	Rupees One Hundred Sixteen and Forty Four Paise Only
3	49.43	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	4652.27	Rupees Four Thousand Six Hundred Fifty Two and Twenty Seven Paise Only
4	58.12	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.878 cum and fine aggragtes @ 0.53cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	Cum	4856.49	Rupees Four Thousand Eight Hundred Fifty Six and Forty Nine Paise Only
5	2.73	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Tonne	61116.3	Rupees Sixty One Thousand One Hundred Sixteen and Thirty Paise Only
6	408	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	Sqm	408.44	Rupees Four Hundred Eight and Forty Four Paise Only
7	190.5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick	Sqm	816.88	Rupees Eight Hundred Sixteen and Eighty Eight Paise Only
8	127.5	Providing one line dressing to granite stone slabs/granite stone masonry as per specifications	Sqm	803.44	Rupees Eight Hundred Three and Forty Four Paise Only
9	1652	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	Nos	395.0	Rupees Three Hundred Ninety Five Only
10	743.4	Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications.	Sqm	33.14	Rupees Thirty Three and Fourteen Paise Only
11	90	Providing and fixing MS Grating 260x260 mm	Nos	75.91	Rupees Seventy Five and Ninety One Paise Only

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of KIRAN GOWDA D (SRI CHANNAKESHAWA ENTERPRISES)	
				In Figures	In Words
12	321.75	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH	Cum	79.72	Rupees Seventy Nine and Seventy Two Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

11/08